



# University of Kashmir

## Office of the Executive Engineer

Phone:-0192420078, 92420405  
Ext:-2040,2053 FAX:- 0194-242135  
Email:-kuexen@uok.edu.in

No: (Corrigendum - New Adm - Block) KU2016-CONS-182

Dated : 07/12/2016

### CORRIGENDUM-II

Sub:- Construction of New Administration Block (P.E.B. Structure) at Main Campus.

Ref :- This Office Tender Notice. No: F(E.Tend.) (New Adm.Block-PEB)UCD/Ku/21 Dated 24-11-2016

**Item No: 44** of the Bill of quantities for the work may please be read as under:-

Read as	Instead of
<p><b>SOLID BISON BOARD PARTITION</b> Providing , Fabricating and fixing of 75mm Thick GI stud full height Bison Board partitions.</p> <ul style="list-style-type: none"> <li>* To have cold rolled GI studs of size 48mm x 0.55mm thick, placed at approx..600mm centre to centre installed onto the boxing at the floor and ceiling channels.</li> <li>* One layer each of tapered edge 10mm thick Bison board Plain , screw fixed with drywall screws of 25mm at 300mm centres to both sides of 48mm GI studs (0.55mm thick having one flange of 34mm and another flange of 36mm made of GI Steel) placed at approx.600mm centre to centre in 50mm floor and ceiling channel (0.55mm thick have equal flanges of 32mm made of GI steel) with joints staggered.</li> <li>* A fixing channel of 99mm width (0.9mm thick having two flanges of 9.5mm each) has to be provided at the horizontal joints of the two boards and as directed by engineer in charge.</li> <li>* Finally square and tapered edges of the boards are to be jointed and finished so as to have a flush look.</li> </ul> <p>The floor channel is to be placed on a clean finished floor on which two line-beads of chalking compound/Silicon sealant have been laid. The floor channel must have two lines of staggered screw fasteners. Care must be taken that the boards are raised 3mm from the floor and in this gap, chalking compound is injected, for successive layers and similarly for the true ceiling channel.</p> <ul style="list-style-type: none"> <li>* Rates to include extra studs and timber rough ground for door window glazings etc.</li> <li>** Rates also to include 12mm groove with adjoining wall , ceiling or partition made with 12mm thick water proof plywood.</li> </ul> <p>Rate shall also include the cost of providing and fixing of 50mm thick Glass wool insulation of 48 density in Roll Form within the G I frame works.</p> <p>Both sides of the frame work to be cladded with single layer of 10mm thick Bison board as per details. The Bison board on the exposed sides to be finished by filling and finishing with Jointing compound, Joint Paper tape and to make surface ready to receive paint. * All Bison board edges to have metal 'L' angles for all free corners.</p> <p><b>Quantity =1500.00 SQM</b></p>	<p><b>FULL HEIGHT SOLID PARTITION - GYPSUM</b> Providing &amp; Fixing 75 mm wide full height GYPSUM PARTITION below the false ceiling level with 48 mm wide studs shall be placed @ 610 mm c/c. framing shall also contain floor cum ceiling channels of 50mm size at floor &amp; ceiling. Two numbers of fixing channels of required length shall also be part of this standard frame work to take the load of soft board / white board. This frame work shall be cladded with one layer of tapered edge 12.5 mm thick gypsum board placed on either side (i.e. total 2 no. of Gypsum Boards of 12.5 mm thickness) screw fixed with dry wall philips screws of 25 mm at 300 mm centers finally square &amp; tapered edges of the boards are to be jointed &amp; finished so as to have a flush look which includes taping , filling and finishing with jointing compound, paper tape &amp; two coats of primer suitable for Gypboard (As per recommended practice of india Gypsum Ltd.)</p> <p>Rate shall also include the cost of providing and fixing of 50mm thick Glass wool insulation of 48 density in Roll Form within the G I frame works. The rate shall also include making 6mm wide groove at the junction of skirting &amp; finished gypboard, necessary cut-outs for back boxes of switchboards, volume controllers &amp; data points. The rate shall also include providing and fixing approx. length 3', 150 mm wide marine plywood support for fixing all type of conduit and metal back boxes. The rate also includes providing 12 mm thick x 150 mm marine plywood at the bottom of partition for fixing vitrified tile skirting. Outer skin of gypsum board shall be cut along the flooring to accommodate the skirting made of marine plywood finished with vitrified tile (skirting shall be measured and paid separately). Mode of measurement shall be area of partition from floor to ceiling. All the GYPSUM BOARDS to be used shall be of India Gypsum Ltd or equivalent of approved make &amp; G I sections shall be of GYPSTEEL or its equivalent.</p> <p><b>Quantity= 2200.6900 SQM</b></p>

The other terms and conditions shall remain the same as per the original NIT and Bill of Quantities.

Executive Engineer



# University of Kashmir

Office of the Executive Engineer

No: (Corrigenda - New Adm. Block) KU2016-CONS-183

Phone:-0192420078, 92420405  
Ext:-2040,2053 FAX:- 0194-242135  
Email:-kuexen@uok.edu.in  
Dated: 07/12/2016

## CORRIGENDUM-III

Sub:- Construction of New Administration Block (P.E.B. Structure) at Main Campus.


Ref :- This Office Tender Notice. No: F(E.Tend.) (New Adm.Block-PEB)UCD/Ku/21 Dated 24-11-2016

Item No: 65 of the Bill of quantities for the work may please be read as under:-

Read as	Instead of
Design fabricate and erect pre-engineered Building structure as per the plan and sections attached and as per detailed description in Schedule-I. Quoted price shall be inclusive of cost of design, material, fabrication, erection, transportation labour and supervision etc. Complete to the satisfaction of Client.  Quantity : ( BUA ) 3085.00 SQM	Design fabricate and erect pre-engineered Building structure as per the plan and sections attached and as per detailed description in Schedule-I. Quoted price shall be inclusive of cost of design, material, fabrication, erection, transportation labour and supervision etc. Complete to the satisfaction of Client.  Quantity : 1 Each

Copy to the:-

1. Director IT&SS for information. He is requested to upload the corrigendum on the University web site.
2. Head Draftsman for information and for uploading of the same on the Departmental website.
3. File
4. Notice Board.

  
Executive Engineer